

## **ASIAN TESTING & INSPECTION SERVICES**

Approved by Govt. Organizations & Third Party Inspection Agencies.

Unit No. 02 & 03, Near Ganesh Temple, Nevali Naka, Kalyan East, Ambarnath MIDC Road, Thane-421506 Maharashtra, India. Email: asian.testinglab@yahoo.com Tel: +91 88509 19087 / 84259 16509 • MSME-UDYAM Registration No:MH-33-0255108

Chemical • Mechanical • Metallography • Corrosion Testing • NDT Services

## **Test Report**

Page 1 of 1

T.C. No.

: A7115-A7119

Issued To.

: SAMS BATH FIXTURES PVT LTD.

Report Date:

Unit No.13 & 31, Sonal Industrial Estate, Pathak Road, Bhayandar (E), Thane-

401105

# Challan Ref. Date

#Description of Sample

: Below mentioned

Sample Received:

#Specification

**Test Started on** 

#PO NO./Date

Test Completed on:

#Qty.

: 05 Nos.

HYDRO PRESSURE TEST

Test Method: ASTM E1003 -13(2018)

Test performed on:

Equipment: Compressor Pump with Pressure Dial Gauge 0 - 4000Psi

Dial Gauge ID.: CORR-36, Cal. Due Dt.:

SR. No.	DESCRIPTION	Marking	CLIENT REQD.PRESSURE Bar(psi)	QTY. IN No.
1	Angle Valve (1/2")	SAMS-AVSTICK-035	10(145.04)	1
2	PVC Connection Pipe(18")	SAMS-PVCCP18-048	10(145.04)	1
3	Connection Pipe(18")	SAMS-SSCCP18-051	10(145.04)	1
4	SS Tube(1Mtr)	SAMS-SSTUB1MTR-070	10(145.04)	1
5	Extention Nipple(2")	SAMS-EXT-003	10(145.04)	1

Note: Pressure Holding Time 10 Sec.

Result: 1- No Leakage & No Pressure Drop Observed.

Remark: Satisfactory

\*\*\*\*\*\*END OF TEST REPORT\*\*\*\*\*

fr. Kushal Pandey Testing In-charge

Checked By

Mr. Munna Singh Lab Head

**Authorised signatory By** 

DISCLAIMER:

The reported test results related only to the sample(s) provided and tested.

The above sample(s) are not drawn by the laboratory.

The Lab is not responsible for any financial / legal liability arising out of any errors or omissions.

This test report cannot be reproduced either in part or in full without the written approval of the lab.

#information provided by customer.

DECISION RULE TO STATE THE CONFORMITY STATEMENT: SIMPLE ACCEPTANCE RULE, as per ILAC G-8: 2019,

i.e. Acceptance Limit (AL)= Tolerance Limit (TL), Results will be rounded off appropriately and will be directly compared with the specification